

Bruhath Bangalore Mahanagara Palike Dasarahalli Zone


Name of Work:Construction of RCC Drains at 8th Cross Left Side in Santhosh Nagara in Ward No.13 Shettyhalli Sub Division.


Est .Cost Rs.20.00 Lakhs									
SI No	Description of Items	Unit	No	L	B	D	Qty	Rate	Amount
1	KSRRB 300-3. Earthwork excavation by manual means in ordinary soil involving in average horizontal throw up to 2m & an average lift upto 1.5m , excavated surface leveled & sides neatly dressed , the disposed earth to be levelled neatly after breaking of clods complete as per specification MORTH/ Chapter 3. Page No. 142/ Item No. 19.1/ PWD SR 2016-17								
	8th Cross	Cum	1	270.00	1.00	1.00	270.00		
	Cross Road		1	75.00	1.00	1.00	75.00		
							345.00	175.96	60706.20
2	Removing B S Slab Drain And Stacking Page No25 Item No 5.32 PWD SR 2016-17								
	8th Cross	Sqm	1	270.00	1.35		364.50		
	Cross Road		1	75.00	1.35		101.25		
							465.75	65.72	30609.09
3	KSRRB 4-1.3 : Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2 Page No.12/ Item No. 4.3/ PWD SR 2016-17								
	8th Cross	Cum	1	270.00	0.90	0.15	36.45		
	Cross Road		1	75.00	0.90	0.15	10.13		
							46.58		
	From Using Available coarse aggregates								
a	Available CA			34.93			41.10	4443.52	182609.07
b	Remaining Balance Qty						5.48	5159.02	28268.39
4	KSRRB 4-1.5 : Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @ 0.43cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Page No.12/ Item No. 4.5/ PWD SR 2016-17								
	Drain Rafi Concrete	Cum	1	270.00	0.90	0.15	36.45		
			1	75.00	0.90	0.15	10.13		
	Side Wall		2	270.00	0.15	0.70	56.70		
			2	75.00	0.15	0.70	15.75		
							119.03	5874.52	699214.74
5	KSRRB 4-6.4 : Providing and removing centering, shuttering, strutting,. propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached1 pilasters, buttresses, plinth cills and string courses cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2 Page No.15/ Item No. 4.31/ PWD SR 2016-17								


	Sqm	4	270.00	0.90		972.00		
		4	75.00	0.90		270.00		
						1242.00	310.58	385740.36
6	KSRB 4.9.2: Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3, TMT bars Fe 500. Page No. 17/ Item No. 4.46.2/ PWD SR 2016-17							
	For RCC Drian	Tonnes	119.03	x	60kgs	7.14		
					Say	7.14	64243.42	458794.38
7	Providing & laying reinforced cement precast slabs of mix CC 1:11/2:3 using 20mm & down size graded Granite metal using HYSD 10mm dia steel @ 100mm c/c both ways & Complete as per specifications.							
	Damaged Slab	Sqm	64	0.60	0.90	34.56		
						34.56	1680.00	58060.80
							Sub Total	1904003.04
8	Add 5% Tender premium							95200.15
9	Rounding off							796.81
							Grand Total	2000000.00
(Rupees Twenty Lakhs Lakhs Only)								

CERTIFICATE

- 1 The Work spot has been inspected and the work found to be necessary
- 2 The Estimate is prepared as per the PWD SR 2016-17
- 3 The Provision made in estimate are adequate and essential
- 4 This area comes under BBMP limits.
- 5 This work is not included in any other estimate.


Asst Engineer
Ward No-13


Asst Executive Engineer
Shettyhalli Sub-Division
BBMP


Executive Engineer
Dasarahalli Zone
BBMP

